

15-175-10192-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Seward County, Sec. 36 Twp. 34 Rge. 32 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C NW SE
Lease Owner LANSEKAN COMPANY, INC.
Lease Name O. T. Wood Well No. 2
Office Address 714 West Olympic Blvd., Los Angeles 15, Calif.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Sept. 12, 1953 19
Application for plugging filed Sept. 13, 1953 19
Application for plugging approved Sept. 11, 1953 19
Plugging commenced Sept. 11, 1953 19
Plugging completed Sept. 12, 1953 19
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation None Depth to top Bottom Total Depth of Well 5345 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand		0'	611'	13-3/8"	651.5'	0'
				8-5/8"	2583.5'	626'
No Oil or Gas bearing formations encountered.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Service Co. mixed and spotted cement plug from 5345' (T.D.) to 4980'; through drill pipe; heavy drilling mud from 4980 to 623'; service company mixed and spotted cement plug from 623' to 586' through drill pipe; heavy drilling mud from 586' to 25'; service company mixed and spotted cement plug from 25' to 5' through drill pipe.

Cement used:

Bottom plug: 100 sacks common cement (in 7-7/8" hole)
Middle " : 30 sacks " " (in 13-3/8" 48# casg.)
Top " : 20 Sacks " " (In 13-3/8" 48# casg.)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Schafer Drilling Company
Address 612 Liberty Bank Bldg., Oklahoma City, Oklahoma


STATE OF Kansas, COUNTY OF Seward, ss.
W. H. Riggins (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Riggins
1020 N. Market, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1953.

Lois Ella Sturdivant
Notary Public.

My commission expires November 16, 1953.



WELL LOG

15-175-10192-0000

LANSEKAN COMPANY, INC.

O. T. Wood #2

C NW SE Sec. 36, 34-S, 32-W, Seward Co.

Drilling Contractor:

Schafer Drilling Company

612 Liberty Bank Building

Oklahoma City, Oklahoma

0 - 611 - Sand, clay, and shale
611 - 883 - Red beds and shale
883 - 1454 - Red beds, sand and shale
1454 - 1618 - Red beds and shale
1618 - 1918 - Red beds and anhydrite
1918 - 2346 - Anhydrite and shale
2346 - 2401 - Lime
2401 - 2455 - Lime and shale
2455 - 2598 - Lime and anhydrite
2598 - 3605 - Lime and shale
3605 - 3718 - Lime
3718 - 3774 - Lime and shale
3774 - 3840 - Lime
3840 - 4120 - Shale
4120 - 4273 - Lime and shale
4273 - 4348 - Shale
4348 - 4456 - Shale and lime
4456 - 4539 - Lime
4539 - 4582 - Lime and shale
4582 - 4659 - Lime
4659 - 4681 - Sandy lime
4681 - 4721 - Lime
4721 - 4772 - Lime and shale
4772 - 4827 - Lime
4827 - 4937 - Lime and shale
4937 - 4955 - Lime
4955 - 5007 - Lime and shale
5007 - 5236 - Lime
5236 - 5274 - Lime and shale
5274 - 5345 - Lime

NOTE:

Above depths corrected to G.L.
G. L. elevation: 2718'

PLUGGING
FILE SEC 36 T 34 R 32W
BOOK PAGE 128 LINE 24