

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

SEWARD

County. Sec. 36 Twp. 34 Rge. 32 W. (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C SW $\frac{1}{4}$ NW $\frac{1}{4}$

Lease Owner LANSEKAN COMPANY, INC.

Lease Name O. T. WOOD Well No. 3-A

Office Address 714 W. Olympic Blvd., Los Angeles 15, Calif.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Abandoned, mechanical trouble 19

Application for plugging filed October 1, 1953

Application for plugging approved Sept. 29, 1953

Plugging commenced Sept. 29, 1953

Plugging completed " " 19 "

Reason for abandonment of well or producing formation Mechanical trouble.

Bottom 2 fts. 8-5/8" Inter. casing, dropped down hole.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

X			

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation None Depth to top Bottom Total Depth of Well 3,291 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand	Water	0'	443'	13-3/8"	642'	0'
				8-5/8"	2,580'	829'
No oil or gas bearing formations encountered.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy drilling mud from 3,291' to 600'. Mixed and spotted 30 sacks cement through drill pipe; 600' - 562'; heavy drilling mud 562' - 20'; mixed and spotted through drill pipe, cement to surface.

10-10-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Schafer Drilling Company

Address 612 Liberty Bank Bldg., Oklahoma City, Oklahoma

STATE OF Kansas, COUNTY OF Seward, ss.

W. H. Riggins (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. H. Riggins

1020 N. Prospect St., Liberal, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of October, 1953

Notary Public

My commission expires 12-18-56



WELL LOG

LANSEKAN COMPANY, INC.
 Wood #3-A
 C SW NW Sec. 36, 34-S, 32-W
 Seward County

Drilling contractor:
 Schafer Drilling Company
 612 Liberty Bank Bldg.
 Oklahoma City, Oklahoma

0'	-	443'	-	Sand, clay, gravel
443'	-	635'	-	Clay, shale
635'	-	910'	-	Red beds
910'	-	970'	-	Gypsum
970'	-	1527'	-	Red beds, shale
1527'	-	1545'	-	Anhydrite
1545'	-	1650'	-	Red bed, shale
1650'	-	2553'	-	Anhydrite and shale
2553'	-	3291'	-	Lime and shale

NOTE: All above depths drillers K.B. (10.0' above G.L.)
 Elevation: 2729' G.L.

PLUGGING
 FILE SEC 36 T 34 R 32W
 BOOK PAGE 133 LINE 6