

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Seward

County. Sec. 35 Twp. 34 Rge. 32 (E) (W)

Location as "NE/CNW/SW" or footage from lines Center of SW - SW

Lease Owner Northern Pump Company

Lease Name Maggie White

Well No. D1

Office Address 1202 Driscoll Bldg., Corpus Christi, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed October 19 51

Application for plugging filed March 28, 19 61

Application for plugging approved March 28, 19 61

Plugging commenced April 3, 19 61

Plugging completed April 19, 19 61

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production February 19 61

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Marrow Depth to top 6036' Bottom 6044' Total Depth of Well 6275' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Marrow	8'	6036	6044	13 3/8"	680'	None
				8 5/8"	2400'	None
				5 1/2"	6110'	2809'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spot 15 sacks of Cement on bottom thru 2" tubing
Fill up 85'-plug from 5960' to 6045'
Pull 2809' of 5 1/2" csg.
Mud up to 25' below base of cellar
Make plug and 5 sacks cement to base of cellar 5' below G.L.

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1961
5-3-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Northern Pump Company
Address 1202 Driscoll Bldg., Corpus Christi, Texas

STATE OF Kansas, COUNTY OF Finney, ss.
Austin Brady

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Austin Brady
Austin Brady
Box 302, Garden City, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of April, 19 61

My commission expires Feb. 20, 1964 Josephine Yardley Notary Public.

15-175-10196-0000

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
APR 19 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: SEWARD

Location: CSW-SW Sec. 35 Twp. 34 Rge. 3Y (E) (W)

Name of Field: _____ Total Depth: 6275'

I have this date completed supervision of plugging of:

Lease Name: MAGGIE WHITE "D" Well No. 1

Operator's Full Name: NORTHERN PUMP CO

Complete Address: 1202 DRISCOLL BLVD CORPUS CHRISTIE, TEXAS

Plugging Contractor: DO TOOLS

Address: _____ License No. _____

Oil Well _____ Gas Well Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5⁰⁰ PM Day 19 Month APRIL Year 1961

The above well was plugged as follows:

13³/₈ - 680' - 8⁷/₈ 2400' - 5¹/₂ 6110'
SPOTTED 15 2400' THRU TUBING FROM 6045' TO
5960' - FILLED W/MUD - PULLED 2309' 5¹/₂" PIPE
FILLED W/MUD TO 25' - CAPPED W/15 2400' TUB TO BASE
OF CELLAR - 8⁷/₈" TUB CIRCULATED IN 13³/₈ FROM
2400' TO 680'

Signed [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

5/11/61
3065-W