

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Seward County, Sec. 30 Twp. 34S Rge. 32 (XX) (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner W. J. Coppinger et al

Lease Name Warden Well No. 1

Office Address 1207 Union National Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 11 1966

Application for plugging filed October 14, 1966

Application for plugging approved Oct. 14 1966

Plugging commenced Oct. 14 1966

Plugging completed Oct. 21 1966

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edd Eves

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6560' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1298	0
				4 1/2	5253	4388

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mix 20 sacks cement to plug off perforations at 5198'. Stop plug at 5000 ft. Shoot pipe loose at 4388 ft. Pull pipe to 700 feet and pump 35 sacks cement at 700 to 600 feet. Finish laying down casing and put 10 sacks cement at 35 feet to 0'. Cut off and cap 8 5/8.

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent Casing Pulling
Address Box 506, Liberal, Kansas

STATE OF Seward Kansas, COUNTY OF Seward, ss.


William F. Dean (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William F. Dean
Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of October, 19 66

My commission expires January 24, 1968

George W. Carrahan
Notary Public.



DRILLING LOG

LEASE OWNER Mallonee-Coppinger Operations, Inc ADDRESS 1207 Union National Bldg
Wichita, Kansas
 LEASE Warden #1 COUNTY Seward, Kansas DESCRIPTION Sec. 30-34S-32W

CASING: SIZE 8 5/8 WEIGHT 23 lb. AMOUNT 1298'

CEMENT: AMOUNT 750 Sx. CIRCULATED: Yes X No

CASING: SIZE 4 1/2 WEIGHT 10.5 AMOUNT 5359 KB

CEMENT: AMOUNT 150 Sx. CIRCULATED: Yes X No

PLUG SET: Ft. TO Ft. CEMENT Sx.

 Ft. TO Ft. CEMENT Sx.

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 14 1966
 CONSERVATION DIVISION
 Wichita, Kansas

FORMATION AND DEPTH


Surface Sand	0	TO	590
Red Bed	590	TO	640
Red Bed & Sand	640	TO	1198
Red Bed	1198	TO	1299
Shale & Anhydrite-Red Bed	1299	TO	1723
Red Bed & Shale	1723	TO	2120
Red Bed, Shale, Anhydrite	2120	TO	2566
Lime & Shale	2566	TO	3246
Lime, Shale, Chalk	3246	TO	3415
Lime & Shale	3415	TO	4778
Lime	4778	TO	5433
Lime & Shale	5433	TO	6367
Lime	6367	TO	6560
TD	6560	TO	

THIS IS A TRUE AND EXACT COPY OF THE FORMATIONS TAKEN FROM THE DAILY DRILLING REPORTS.

Executed this 26th day of September 19 66

By *A. W. Mahoney*

IN WITNESS WHEREOF, I have hereunto set my hand and affixed my official seal the day and year above written.



George W. Carnahan
Notary Public

MY COMMISSION EXPIRES: January 24, 1968