

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Flinney State Office Building
 30 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-175-21103 - 0000

LEASE NAME CONDIT SW UNIT

WELL NUMBER 1-3

990 Ft. from S Section Line

1850 Ft. from E Section Line

SEC. 24 TWP. 34S RGE. 33 (E) or (W)

COUNTY SEWARD

Date Well Completed 1-10-90

Plugging Commenced 12-11-97

Plugging Completed 12-14-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well INPUT

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-1-97 (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation L. CHESTER Depth to Top 6276 Bottom 6305 T.D. 6420

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
L. CHESTER	INJ	6276	6305	8-5/8	1545	4'
				5-1/2	6420	2606'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. MIRU SARGENT&GORTON'S. PMP 3 SXS HULLS + 25 SXS CMT TO PLG 6276-6076. PULL FREEPOINT, CUT OFF 5-1/2 CSG @ 2606. PMP 25 SXS CMT TO PLG 1575-1425. POH TO 650. PMP 40 SXS CMT TO PLG 650 TO 550. POH TO 40'. PMP 25SXS CMT TO PLG 4' TO SE. CUT OFF AND CAP 8-5/8 CSG 4' BELOW GL. RETRIEVED 65 JTS 5-1/2" CSG. NOTIFIED KCC REP GARY WINTERS

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 498A, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young
 SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

STATE CORPORATION COMMISSION (Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 5th day of February, 1998

FEB 9

Shirley J Childers
 Notary Public

My Commission Expires: _____

