

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20262-000/

LEASE NAME Brown C

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1320 FSL Ft. from S Section Line

1980 FEL Ft. from E Section Line

SEC. 17 TWP. 34S RGE. 33 (W)

COUNTY Seward

Date Well Completed 7/75

Plugging Commenced 4/2/97

Plugging Completed 4/14/97

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 300, Tulsa, OK 74102

PHONE (918) 561-3548 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 2, 1997 (date)

by Mr. David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? yes

Producing Formation Toronto & Morrow Depth to Top 4328-4335 Bottom T.D. 6070'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	Oil	4328	4335	8 5/8"	Unknown	
Morrow	Oil	6036	6048	5 1/2"	Unknown	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Set CIBP at 6010'. Dumped 2 sx cmt on plug. Set 2nd plug at 4260'. Dumped 2 sx cmt on plug. Freed 5 1/2" csg at 2574 to 2617'. Shot squeeze hole at 2999-3004'. Pumped 120 sx cmt. Cut off csg at 2591'. Pumped 80 sx cmt spot plug at 2591'. Pumped 50 sx cmt plug at 1679'. Spotted 50 sx cmt plug at 800'. Top off hole w/10 sx cmt plug from 40 to 4'.

Name of Plugging Contractor Gibson Well Service License No. 5866

Address Liberal, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF Tulsa, ss.

RAYMOND HUI

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Raymond Hui

(Address) P. O. Box 300, Tulsa, OK 74102-0300

SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 97

Karen Anne Wells
Notary Public

My Commission Expires: 9-22-97