

15-175-30003-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME CONDIT UNIT

WELL NUMBER 5-2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 13 TWP. 34 RGE. 33 (E) or (W)

COUNTY Seward

Date Well Completed 2/3/65

Plugging Commenced 2/24/88

Plugging Completed 2/26/88

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Water injector

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/17/87 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? Drillers log Filed w/Form CP-1

Producing Formation L. Chester Depth to Top 6268 Bottom 6286 T.D. 6376

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
L. Chester	Oil	Surf	1609	8-5/8	1609	0
		Surf	6375	4-1/2	6375	1403

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Rigged up Sargents. Pmpd 25 sxs cmt, 1 sx hulls 6286-6000. Cut off csg at 1403. Pmpd 50 sxs cmt 1500-1400, pmpd 30 sxs cmt 650-550, pmpd 12 sxs cmt 40-0. Cut off and capped 8-5/8 csg 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901


STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Manager (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct so help me God.

MAY 19 1988

(Signature) M. L. Pease

(Address) P. O. Box 351, Liberal, KS 67905



Subscribed and sworn to before me this 18<sup>th</sup> day of May, 19 88  
Beverly J. Williams  
Notary Public  
November 21, 1990

DRILLER'S LOG

WELL NAME: Rubank "B" No. 2 ; COMPANY OPERATING: Anadarko Production Company  
 ADDRESS of COMPANY: P. O. Box 351, Liberal, Kansas

WELL LOCATION: C 1/4 NE 1/4 NE 1/4,  
630 ft. ~~NORTHWEST~~ south of north line  
709 ft. ~~EAST~~ west of east line; Sec. 13, Twp. 34N, Rge. 33W, Sevier County, Kansas

DRILLING STARTED 1-12, 1965; DRILLING COMPLETED 1-29, 1965  
 WELL COMPLETED 2-3, 1965; WELL CONNECTED \_\_\_\_\_, 19\_\_\_\_

ELEVATION: 2021.71 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
<u>Chester</u>	<u>6276</u>	<u>6280</u>	<u>8</u>	<u>500</u>	<u>15% NE</u>

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
<u>8-5/8</u>	<u>1609'</u>	<u>850</u>	
<u>4-1/2"</u>	<u>6375'</u>	<u>210</u>	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
<u>Sand &amp; clay</u>	<u>0</u>	<u>620</u>			
<u>Red bed, Gypsum &amp; sand</u>	<u>620</u>	<u>1340</u>			
<u>Red bed &amp; gypsum</u>	<u>1340</u>	<u>1614</u>			
<u>Anhydrite &amp; red bed</u>	<u>1614</u>	<u>2144</u>			
<u>Anhydrite &amp; shale</u>	<u>2144</u>	<u>2737</u>			
<u>Shale &amp; lime</u>	<u>2737</u>	<u>3067</u>			
<u>Lime</u>	<u>3067</u>	<u>3722</u>			
<u>Shale &amp; lime</u>	<u>3722</u>	<u>4662</u>			
<u>Lime</u>	<u>4662</u>	<u>5432</u>			
<u>Shale &amp; lime</u>	<u>5432</u>	<u>6238</u>			
<u>Lime</u>	<u>6238</u>	<u>6376</u>			
<u>Total Depth</u>	<u>6376</u>				

RESULTS of INITIAL PRODUCTION TEST: Swabbed & flowed 250.07 bbls. in 22-1/2 hours.