

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 175-20,800-0000

LEASE NAME Hampton

WELL NUMBER 17-4

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 17 TWP. 34S RGE. 34 (E) or (W)

COUNTY Seward

Date Well Completed 2-6-85

Plugging Commenced 2-6-85

Plugging Completed 2-6-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Flynn Energy Corp.

ADDRESS 2431 East 61st St., Suite 150, Tulsa, OK 74136

PHONE#(918) 749-0469 OPERATORS LICENSE NO. 6958

Character of Well Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? NO If not, is well log attached? No - Will be Filed w/ACO-1.

Producing Formation None Depth to Top _____ Bottom T.D. 6450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Water	4390	4440	8-5/8"		
Marmaton	Water	5110	5190	8-5/8"	1717	None
Mississippian	Water	6107	6188			
St. Genevieve	Water	6390	6450			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Hole loaded with 9.1# of mud, spotted 50 sx plug @ 1800' - set 50 sx plug @ 750'.
Set 20 sx plug from 40' to surface. Plug rate hole w/15 sx and mouse hole with 10 sx. Cut off head. Welded plate over same.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton - Service Drilling License No. 5287-5987

Address Liberal, Kansas - Borger, Texas

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Richard R. Luce (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.
STATE CORPORATION COMMISSION

(Signature) Richard R. Luce

(Address) 2431 E. 61st St., Suite 150, Tulsa, OK

FEB 28 1985

SUBSCRIBED AND SWORN TO before me this 26th day of February, 19 85
Wichita, Kansas

Dorena P. Pugh
Notary Public

My Commission Expires: June 24, 1986