

15-129-00029-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92
RECEIVED
KANSAS CORPORATION COMMISSION
JAN 15 1993
CONSERVATION DIVISION
WICHITA, KS

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 8-30-56 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 549
(owner/company name) (operator's)

ADDRESS P. O. Box 351 CITY Liberal

STATE Kansas ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE Wacker WELL# 1-7 SEC. 7 T. 34S R. 41 (East/West)

- - C - SE SPOT LOCATION/QQQQ COUNTY Morton
1320 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)
1320 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE - SET AT - CEMENTED WITH - SACKS
SURFACE CASING SIZE 8 5/8 SET AT 1467 CEMENTED WITH 800 SACKS
PRODUCTION CASING SIZE 5 1/2 SET AT 4533 CEMENTED WITH 800 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3017-3122' OA (Topeka)

ELEVATION 3432.5 T.D. 5288 PBDT 3124 ANHYDRITE DEPTH 1380
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Place 35 sxs cmt from 2900-3122' by displacing with 72 bbls mud. Shoot off 5 1/2" csg at freepoint & spot 50 sxs (200' plug) at cut off. Spot 10 sxs cmt from 33-3'. Cut off csg 3' below ground level & cap. Restore location.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED?

If not explain why? *Driller's Log is attached.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin Johnson PHONE# (316) 697-2188

ADDRESS P. O. Drawer X City/State Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargent's Casing Pulling Service KCC LICENSE # 6547
(company name) (contractor's)

ADDRESS 620 S. Lincoln, Liberal, KS 67901 PHONE # (316) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon Approval

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: January 14, 1993 AUTHORIZED OPERATOR/AGENT: C M Stephens, Jr.
(signature)

C M Stephens, Jr., Senior Staff Reservoir Engineer

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

January 20, 1993

Anadarko Petroleum Corp
Box 351
Liberal KS 67905-0351

Wacker 1-7
1320' FSL-1320' FEL
Sec. 07-34-41W
Morton County

Dear Mr. C. M. Stephens, Jr.

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760