

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-129-003330000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE BAKER WELL# 1-33 SEC. 33 T. 33S R. 41 (XXXX/West)

- C - NW - SE SPOT LOCATION/QQQQ COUNTY MORTON

1980 FEET (in exact footage) FROM X[Ⓢ] (circle one) LINE OF SECTION (NOT LeaseLine)

1980 FEET (in exact footage) FROM [Ⓢ]X (circle one) LINE OF SECTION (NOT LeaseLine)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 645' CEMENTED WITH 350 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 2253' CEMENTED WITH 250 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2074-2149 (OA), CIBP @ 2161',
2168-2179.

ELEVATION 3365 - T.D. 2260 PBDT 2161 ANHYDRITE DEPTH NA
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE
PROPOSED METHOD OF PLUGGING NOTIFY DISTRICT OFFICE 5 DAYS PRIOR TO PLUGGING. MIRU
CASING PULLERS. MIX AND PUMP 2 SKS HULLS AND 15 SKS CLASS H CMT W/6% GEL FROM 2024' TO
2149'. DISPLACE CMT W/9 PPG MUD. DETERMINE FREE POINT. SHOOT OFF 4 1/2" CASING. TOH W/CSG
TO 695'. MIX & SPOT 65 SKS CMT 695' TO 495'. TOH W/CSG TO 45'. MIX AND SPOT 15 SKS
CLASS H CMT FROM 45' TO SURFACE. TOH W/REMAINING CSG. CUT OFF AND CAP 8 5/8" CSG 3'
BELOW GL. INSCRIBE WELL NAME, NUMBER, LEGAL DESCRIPTION, AND PLUGGING DATE ON CAP.
RDMO CASING PULLERS. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? FILED WITH ORIGINAL ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

TERRY LEWIS PHONE# (316) 697-2188

ADDRESS P.O. DRAWER X City/State ELKHART, KANSAS 67950

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

DATE: 5/26/98 AUTHORIZED OPERATOR/AGENT: Shawn Young

SHAWN YOUNG (signature)
DIVISION PRODUCTION ENGINEER

RECEIVED
MAY 29 1998
COMMISSION
DIVISION
Kansas



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

July 28, 1998

Anadarko Petroleum Corporation
PO Box 351
Liberal, Ks. 67905-0351

Baker #1-33
API 15-12900333
C NW SE
Sec. 33-33S-41W
Morton County

Dear Terry Lewis,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888