

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 1512920530-0002 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)

ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO

STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600

LEASE LOW D WELL# 6 SEC. 18 T. 33 R. 40 (xxxx/West)

S/E - NE - SE SPOT LOCATION/QQQQ COUNTY MORTON

1650 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#                     

CONDUCTOR CASING SIZE                      SET AT                      CEMENTED WITH                      SACKS

SURFACE CASING SIZE 8 5/8 SET AT 1485 CEMENTED WITH 750 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 5825 CEMENTED WITH 220 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: SEE ATTACHED WELL BORE DIAGRAM.

ELEVATION 3266 /                      T.D. 5825 PSTD 3052 ANHYDRITE DEPTH                       
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING PMP 30 SXS CMT & 2 SXS HULLS DOWN CSG. DISPLACE WITH 9PPG MUD. WOC AND TAG. SHOOT OFF 5 1/2 CSG 1550. SPOT 100 SXS CMT AT 1550. DISPLACE WITH 9PPG MUD. WOC & TAG. SPOT 40 SXS CMT AT 750. SPOT 10 SXS CMT AT 53 TO SURFACE. CUT OFF AND CAP CSG 3' BELOW GL. RDMO. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

TERRY LEWIS PHONE# (620) 697-3609

ADDRESS PO BOX 720 City/State ELKHART, KS 67950

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/7/2002 AUTHORIZED OPERATOR/AGENT: Craig R. Walters  
CRAIG R. WALTERS, P.E. (signature)  
DIVISION PRODUCTION ENGINEER

RECEIVED

MAR 11 2002

KCC WICHITA



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Anadarko Petroleum Corporation  
17001 Northchase Drive  
Houston, TX 77060

March 15, 2002

Re: Low D #6  
API 15-129-20530-00-02  
S2NESE 18-33S-40W, 1650 FSL 660 FEL  
MORTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely,  
Handwritten signature of David P. Williams in black ink.

David P. Williams  
Production Supervisor