

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

15-129-20075-0000

API NUMBER 3/23/72 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

3/90

LEASE OPERATOR Matagorda Island Exploration Corporation OPERATORS LICENSE NO. 3316

ADDRESS P.O. Box 351, Liberal, KS 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) LOW "D" WELL NO. 4 WELL LOCATION S/2 SE COUNTY Morton

SEC. 18 TWP. 33S RGE. 40 (E) or (W) TOTAL DEPTH 5760' PLUG BACK TD 5731'

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 1478' CEMENTED WITH 700 SACKS

CASING SIZE 4 1/2" SET AT 5759' CEMENTED WITH 275 SACKS

PERFORATED AT 5684'-5690' (St. Louis)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set cement retainer above perfs and squeeze perfs with 25 sxs LWL cement. Sting out of retainer and TOH w/tbg. Locate free-point and cut off casing. (over)

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No\* IS ACO-1 FILED? No\*  
(If not, explain)\*Well record and logs already on file.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: \_\_\_\_\_

Marvin B. Johnson PHONE # (316) 697-2188

ADDRESS P.O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: \_\_\_\_\_

M. L. Pease (Operator or Agent)  
Division Production Manager

DATE: 9/11/89

①

RECEIVED  
STATE CORPORATION COMMISSION  
Wichita, Kansas  
15 1099  
490

- (1)\* Spot 50' foot cement plug at cut-off and TOH w/ casing.
- (2)\* Spot 50' foot cement plug in and out of surface casing.
- (3)\* Spot 50' foot cement plug from 50' back to surface.
- (4) Cut-off casing 3' below ground level and weld on cap.
- (5) Restore location.

\*Hole will be filled with heavy mud (36 viscosity) between all cement plugs.



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
KEITH R. HENLEY CHAIRMAN  
RICH KOWALEWSKI COMMISSIONER  
MARGALEE WRIGHT COMMISSIONER  
JUDITH McCONNELL EXECUTIVE DIRECTOR  
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE

DEC 18 1989

EXPIRES

September 18, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

Matagorda Island Exploration Corporation  
P.O. Box 351  
Liberal, KS 67905-0351

Low "D" 4  
S/2 SE  
18-33-40W  
Morton County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht  
Director

District: # 1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760