

RECEIVED

SEP 27 2002

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

KCC WICHITA WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-129-21398-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO

STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600

LEASE DAVISON WELL# A-3 SEC. 20 T. 33S R. 40 (xxxx/West)

- - - - - SW SPOT LOCATION/QQQQ COUNTY MORTON

2610 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM X/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 1535 CEMENTED WITH 470 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 5888 CEMENTED WITH 240 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: PERFS: 5830-5846, 5620-5632. CIBP @ 5730

ELEVATION 3308 / XX T.D. 5900 PBD 5730 ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING TOH WITH 2 3/8 TBG. DUMP 2 SXS HULLS AND 25 SXS CMT FROM 5730-5520. DISPLACE WITH 9 PPG MUD. TAG. PULL FREE POINT AND SHOOT OFF 5 1/2 CSG @ +/- 500 ABOVE FREE POINT. SPOT 30 SXS CMT AT SHOOT OFF POINT. DISPLACE WITH 9 PPG MUD. TAG. TOH SPOT 60 SXS CMT FROM 1600 TO 1400. DISPLACE WITH 9 PPG MUD. TAG. SPOT 40 SXS CMT FROM 600 TO 480. DISPLACE WITH 9 PPG MUD. TAG. TOH AND SPOT 10 SXS CMT FROM 40 TO 4. CUT OFF AND CAP 8 5/8 CSG 4 FEET BELOW GL.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

TERRY LEWIS PHONE# (620) 697-2188

ADDRESS PO BOX 720 City/State ELKHART, KANSAS

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/24/2002 AUTHORIZED OPERATOR/AGENT: Craig R. Walters

CRAIG R. WALTERS, P.E. (Signature)
DIVISION PRODUCTION ENGINEER



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation
1201 Lake Robbins Drive
The Woodlands, TX 77380

October 01, 2002

Re: DAVISON A #3
API 15-129-21398-00-00
W2SW 20-33S-40W, 2610 FSL 1320 FWL
MORTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888

Sincerely
A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor