

15-129-10419-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 12-15-54 Spud Date _____

LEASE NAME Interstate Unit

WELL NUMBER 67

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 29 TWP. 34 SRGE. 43 (S) or (W)

COUNTY Morton

Date Well Completed 12-31-54

Plugging Commenced 7-5-94

Plugging Completed 7-8-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, KS 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-8-94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Drillers Log Filed If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.O. 4252

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1200	5'
				5 1/2	4252	1240'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU csg pullers. TIH w/1 1/4" tbg to 4100'. RU pmp truck. Circ hole w/9 ppg mud. Pmp 10 sxs Class "H" cmt to spot plug on CIBP from 4100-4000'. TOH w/1 1/4" tbg. Pull free point and shot 5 1/2" csg @ 1240'. Circ hole w/9 ppg mud, spot 50 sxs Class "H" cmt from 1240-1090'. 35 sxs Class "H" cmt @ 650-550', 10 sxs Class "H" cmt plug @ 40-5'. Cut off and cap 8 5/8" csg 5'
(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, Oklahoma 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Leslie I. Barnes (Employee of Operator) or (~~XXXXXXXX~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leslie I. Barnes
Leslie I. Barnes, Sr. Tech. Asst.

(Address) P.O. Box 351, Liberal, KS 67905-0351

RECEIVED
KANSAS CORPORATION COMMISSION

DESCRIBED AND SWORN TO before me this 1st day of August, 19 94

8-09-94
CONSERVATION DIVISION
WICHITA, KS Commission Expires _____

CHERYL STEERS
Notary Public - State of Kansas
My Appl. Expires 6-4-97

Cheryl Steers
Notary Public