

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-20,565-0000

LEASE NAME Interstate Unit

WELL NUMBER 95

3960 Ft. from S Section Line

96 Ft. from E Section Line

SEC. 29 TWP. 34S RGE. 43 (E or W)

COUNTY Morton

Date Well Completed 1/16/82

Plugging Commenced 10/28/87

Plugging Completed 10/30/87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#( 316 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/27/87 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 4105 Bottom 4120 T.D. 4281

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>4105</u>	<u>4120</u>	<u>8.625</u>	<u>1193</u>	<u>0</u>
				<u>5.5</u>	<u>4280</u>	<u>2038</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP set @ 4050. Spot 20 sxs common cement thru tubing from 4050-3900. Shot off 5.5" casing @ 2038. Spotted 30 sxs cement 2058-1938, spotted 60 sxs cement from 1250-1100. Spotted 70 sxs cement from 650-480. Pushed wooden wiper plug to 50'. Pumped 20 sxs cement from 50-3'. Cut off casing and cap well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or ~~XXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) Box 351, Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 30<sup>th</sup> day of December, 19 87

Beverly J. Williams

Notary Public

My Commission Expires: Nov. 21, 1987

CONSERVATION DIVISION  
Wichita, Kansas

12-31-87