

15-129-10446-0000

Formerly ROLL No. 5

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME Interstate Unit

WELL NUMBER 54

3960 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 29 TWP. 34S RGE. 43 (E) or (W)

COUNTY Morton

Date Well Completed 3/3/57

Plugging Commenced 11/1/87

Plugging Completed 11/3/87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/27/87 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? None available

Producing Formation Morrow Depth to Top 4148 Bottom 4156 T.D. 4240

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>4148</u>	<u>4156</u>	<u>8.625</u>	<u>1175</u>	<u>0</u>
				<u>5.5</u>	<u>4239</u>	<u>1717</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP set @ 4039. Spotted 20 sxs cement thru tubing from 4039 to 3889. Shot off 5.5" casing 1717, spotted 30 sxs cement from 1717-1617. Spotted 50 sxs cement from 1250-1100, spotted 70 sxs cement from 650-480. Push wooden wiper plug to 50'. Pump 20 sxs cement 50-3'. Cut off 8.625" casing 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss. 12-31-87  
WFC # 1087

M. L. Pease, Division Production Manager (Employee of Operator) DOOR OPERATOR of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 87

Beverly J. Williams  
Notary Public

My Commission Expires: Nov. 21, 1990