

15-129-10422-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 2-7-55LEASE NAME INTERSTATE UNITWELL NUMBER 64

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line660 Ft. from E Section LineSEC. 29 TWP. 34S RGE. 43 ~~XXX~~ (W)COUNTY MortonDate Well Completed 2-7-55Plugging Commenced 2-18-91Plugging Completed 2-18-91LEASE OPERATOR Anadarko Petroleum CorporationADDRESS P. O. Box 351, Liberal, Kansas 67905-0351PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-6-91 (date)by Dick Kapp (KCC District Agent's Name).Is ACO-1 filled? Yes If not, Is well log attached? _____Producing Formation Morrow Depth to Top 4196 Bottom 4210 T.D. 4278

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1200	None
				5 1/2	4274	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Mix & pmp 2 sxs hulls & 50 sx cmt dwn 2 3/8" fg tbq, press to 1000#. Mix & pmp 60 sxs cmt dwn 5 1/2" & 8 5/8" ann, press to 2000#. Cut off & cap 8 5/8" 5 1/2", & 2 3/8" 3' below GL.
Restore location. KCC state witness on location.

(If additional description is necessary, use BACK of this form.)Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547Address 620 S. Lincoln, Liberal, Kansas 67901NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum CorporationSTATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams - Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Beverly J. Williams
(Address) Beverly J. Williams - Engineering Tech.
P.O. Box 351, Liberal, KS 67905-0351

RECEIVED
STATE CORPORATION COMMISSION

APR 03 1991 SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 91

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: _____



Notary Public

Form CP-4
Revised 05-88