

15-129-10418-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 11-20-54

LEASE NAME Interstate Unit

WELL NUMBER 61*

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 29 TWP. 34S RGE. 43 XXX or (W)

COUNTY Morton

Date Well Completed 11-20-54

Plugging Commenced 7-30-91

Plugging Completed 8-1-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-29-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, Is well log attached? _____

Producing Formation Morrow Depth to Top 4170 Bottom 4207 T.D. 4240

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1200	0
				5 1/2	4238	1240

AUG 26 1991

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set MIRU csg pullers. Rel pkr & circ hole w/9.0 ppg mud. Spot 25 sxs hulls & 20 sxs cmt from 4179-4079'. Ld 2 3/8 tbg & pkr. Shot off 5 1/2 csg @ 1240'. Spot 70 sxs cmt from 1240-1040', 35 sxs cmt from 650-550'. 10 sxs cmt from 33-3'. Cut off and cap 8 5/8 csg 3' below ground level & restore location. KCC Rep - Glenn Barlow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams - Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

*Formerly J. M. Huber Corp., USA "C" No. 4

(Signature) Beverly J. Williams
Beverly J. Williams - Eng. Technician
(Address) P.O. Box 351, Liberal, Kansas 67905

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 19 91

CHERYL STEERS Notary Public
Notary Public - State of Kansas
My App. Expires 6-4-93

My Commission Expires: _____