

15-129-10420-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 12-7-54

LEASE NAME INTERSTATE UNIT

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 69

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 29 TWP. 34S RGE. 43 ~~XXX~~ or (W)

COUNTY Morton

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 12-7-54

Character of Well Injection Well

Plugging Commenced 1-23-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-25-90

The plugging proposal was approved on 1-22-90 (date)

by Glenn Barlow (KCC District Agent's Name).

Physical Productivity

Is ACO-1 filed? Report If not, Is well log attached? NA

Producing Formation Purdy Morrow Depth to Top 4212 Bottom 4230 T.D. 4280

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil	4212	4232	8 5/8	1198	0
				5 1/2	4280	1250

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH W/2 3/8 tbg to top of pkr w/plug @ 4050. Spot 20 sxs cmt from 4074-3900 on top of pkr & plug. Circ hole w/9 ppg DM. TOH w/tbg. Shoot off csg @ 1416 (would not pull), reshot @ 1256. Spot 50 sxs cmt from 1250-1100, 35 sxs cmt from 650-550 & 10 sxs cmt from 40-0'. Cut off 8 5/8 csg 3' below GL & cap. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Morton, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease  
(Address) M. L. Pease, Division Production Mgr. P.O. Box 351, Liberal, KS 67905-0351

STATE OF KANSAS  
FEB 23 1990

SUBSCRIBED AND SWORN TO before me this 18th day of February, 19 90

COMMISSIONER OF CORP. DIVISION  
Wichita, Kansas

My Commission Expires: \_\_\_\_\_

CHERYL STEERS  
Notary Public - State of Kansas  
My Appt. Expires 6-1-93

Cheryl Steers  
Notary Public