

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10442-0001

API NUMBER November, 1956

LEASE NAME Interstate Unit *

WELL NUMBER 51

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 29 TWP. 34S RGE. 43 (EX) (W)

COUNTY Morton

Date Well Completed November, 1956

Plugging Commenced 8-27-91

Plugging Completed 8-27-91

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-26-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, Is well log attached? _____

Producing Formation Morrow Depth to Top 4114 Bottom 4166 T.D. 4217

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1214	0
				5 1/2	4215	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set Pmpd 2 sxs hulls & 110 sxs cmt down 2 3/8 cmtd FG tbg from 3'-4114'. Pmpd 120 sxs cmt down 5 1/2 and 8 5/8 annulus to 500' and 10 sxs cmt from 33'-3'. Cut off 3' below GL and cap well. State Rep - Glenn Barlow witnessed.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams - Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

*Formerly Musgrove Roll No. 1

(Signature) Beverly J. Williams

(Address) Beverly J. Williams - Eng. Tech.
P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 16th day of September, 19 91

My Commission Expires: _____



Cheryl Steers
Notary Public