

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-129-20,516-0000

LEASE NAME ROLL "C"

WELL NUMBER 1-29

990 Ft. from N Section Line

990 Ft. from E Section Line

SEC. 29 TWP. 34S RGE 43 (E) or (W)

COUNTY MORTON

Date Well Completed 05/28/81

Plugging Commenced 04/15/97

Plugging Completed 04/16/97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04/01/97 (date)

by MR. GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation REDCAVE Depth to Top 1216' Bottom 1234' T.D. 1234'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
REDCAVE	GAS	1216'	1234'	8-5/8"	450'	4'
				5-1/2"	1192'	4'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU PU. TH W/1-1/4" TBG TO 1190'. PMP CMT PLG FROM 1190-975' W/25 SXS CMT W/2 SXS HULLS. PULL TBG TO 500' PMPD CMT PLG FROM 500-328' W/20 SXS CMT. PULL TBG TO 40'. PMP CMT PLG FROM 40'-SF. CUT OFF 8-5/8" & 5-1/2" CSG 4' BELOW-GL. RESTORE LOCATION. KCC REP: GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151 6-19-97

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman
 (JOHN A) BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 18th day of June, 1997

Shirley Childers
 Notary Public

My Commission Expires: 11/14/98

