

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Morton County, Sec. 29 Twp. 34S Rge. (E) 43 (W)

Location as "NE/CNWxSWx" or footage from lines C NW NE
Lease Owner Musgrove Petroleum Corporation
Lease Name ROLL Well No. 2
Office Address 801 Union Center, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed October 26, 1956
Application for plugging filed verbally - October 25, 1956
Application for plugging approved verbally - October 25, 1956
Plugging commenced October 26, 1956
Plugging completed October 26, 1956
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4220 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1163'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 50 sx cement on bottom at 4220';
spotted 25 sx cement at 2700';
spotted 25 sx cement at 650' and
spotted 15 sx cement at 35'.

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Musgrove Petroleum Corporation
Address 801 Union Center, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Gordon L. Koelling (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
801 Union Center, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of October, 1956

Beah Joyce Dyke
Notary Public.

My commission expires June 16, 1959.

PLUGGING
FILE SEC. 29 T. 34 R. 43W
BOOK PAGE 111 LINE 8

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: ROLL #2
 LOCATION: C NW NE, Sec. 29-34S-43W
 Morton County, Kansas
 COMMENCED: October 12, 1956
 COMPLETED: October 26, 1956.

0	313	Surface sand, shale & shells
313	612	Red bed & sand & clay
612	768	Red bed & Anhydrite
768	950	Sand, shale & shells
950	1120	Lime streaks & shale
1120	1153	Shale & shells
1153	1165	Anhydrite
1165	1250	Anhydrite & shale
1250	1690	Shale, sand & shells
1690	1985	Shale & lime shells
1985	3890	Shale & lime
3890	4075	Lime
4075	4220	Sand, lime & shale
	4220	Rotary Total Depth

Set 8-5/8" surface pipe at 1163' with 675 sacks Posmix, 3% calcium chloride.
 Dry and Abandoned.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the ROLL #2, C NW NE, Section 29-34S-43W, Morton County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 30th day of October, 1956.

Earl Jaye Hepp
 Notary Public

My commission expires June 16, 1959.

RECEIVED
 CORPORATION COMMISSIONER

PLUGGING
 FILE SEC 29 T 34 R 43W
 BOOK PAGE 111 LINE 8