

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Morton County, Sec. 29 Twp. 34 Rge. 43 (E) (W)

Location as "NE/CNW'SW" or footage from lines C NE NW

Lease Owner Musgrove Petroleum Corporation

Lease Name SWITZER Well No. 3

Office Address 518 Petroleum Building, Wichita, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed February 4, 19 56

Application for plugging filed verbally - February 3, 19 56

Application for plugging approved verbally - February 3, 19 56


Plugging commenced February 4, 19 56

Plugging completed February 4, 19 56

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Verbally - yes - written 2-8-56



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4505 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1179'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 600'
Set 1st plug at 600' w/35 sx cement
Filled hole with heavy mud to 40'
Set 2nd plug at 40' w/15 sx cement

2-10-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Gordon L. Koelling (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of February, 1956

Reah Joyce Hefke
Notary Public.

My commission expires June 16, 1959

PLUGGING
FILE SEC 29 T 34 R 43 W
BOOK PAGE 37 LINE 14

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: SWITZER #3
 LOCATION: C NE NW Sec. 29-34-43
 Morton County, Kansas
 COMMENCED: December 30, 1955
 COMPLETED: February 4, 1956

0	220	Surface sand & shale
220	315	Red bed, shale & shells
315	342	Sand
342	460	Shale & shells
460	580	Red bed & lime shells
580	660	Shale & shells
660	974	Lime & shale
974	1168	Sand, shale & lime
1168	1180	Anhydrite
1180	1800	Anhydrite & shale
1800	2140	Shale & shells
2140	2888	Shale & lime
	2888'	Whipstock

WHIPSTOCK:

1724	1780	Shale
1780	1909	Shale & shells
1909	1967	Shale
1967	1990	Shale & shells
1990	2299	Shale & lime
2299	2372	Shale & shells
2372	3450	Shale & lime
3450	3548	Lime & shale streaks
3548	3665	Shale & lime
3665	3635	Lime
3635	3920	Shale & lime
3920	4175	Lime
4175	4230	Lime & shale
4230	4285	Lime
4285	4444	Lime & shale
4444	4505	Lime
	4505	Rotary T. D.

Set 8-5/8" surface pipe at 1179' with 657 sacks Fosmix, 2% cal. chloride. Dry and Abandoned.

ELEVATION :	3494' K. B.	Morrow Shale	4094'	(- 600)
SCHLUMBERGER TOPS:		Purdy Sand	4200'	(- 706)
Topeka	2718' (/ 776)	Upper Keyes	4466'	(- 972)
Lansing	2945' (/ 549)	Lower Keyes	4504'	(-1010)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the SWITZER #3, C NE NW, Section 29-34S-43W, Morton County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION.

By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of February, 1956.

Reed J. Hefke
 Notary Public

PLUGGING
 FILE REC 29-34-R 43W
 BOOK PAGE 37 LINE 14