

15-129-10220-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA (SPUD 12-29-63)

LEASE NAME SWITZER "A"

WELL NUMBER 2

1390 Ft. from S Section Line

1420 Ft. from E Section Line

SEC. 29 TWP. 34S RGE. 43 (E) or (W)

COUNTY MORTON

Date Well Completed 01/08/64

Plugging Commenced 07/09/97

Plugging Completed 07/10/97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 06/27/97 (date)

by MR. GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation RED CAVE Depth to Top 1194' Bottom 1227' T.D. 1227'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
RED CAVE	GAS	1194'	1227'	7"	1194'	4'
				5-1/2"	2884'	4'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU PU & PMP TRUCK. RIH W/1-1/4" TBG TO 1194'. DIG CELLAR & PIT. PMP 3 SXS HULLS & 40 SXS CMT TO PLG OPEN HOLE FROM 1194' TO 994'. PULL 1-1/4" TBG TO 994' & CIRC HOLE W/MUD. PULL TO 650'. PMP 40 SXS CMT TO PLG FROM 650' TO 450'. PULL TO 60' PMP 12 SXS CMT TO PLG FROM 60' TO 4'. CUT OFF & CAP 7" CSG. 4' BELOW GI INSCRIBE CAP. RDMO PU & PMP TRUCK. KCC REP - GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman
JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 21st day of August, 1997.

Shirley Childers
Notary Public

My Commission Expires _____

