

STATE OF KANSAS  
STATUTE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 4-6-54 Drill Date \_\_\_\_\_  
LEASE NAME Interstate Unit  
WELL NUMBER 65\*  
1320 Ft. from S Section Line  
1320 Ft. from E Section Line  
SEC. 29 TWP. 34S RGE. 43 (E) or (W)  
COUNTY Morton  
Date Well Completed 4-29-54  
Plugging Commenced 3-17-93  
Plugging Completed 3-25-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation  
ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351  
PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549  
Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-16-93 (date)  
by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? -  
Producing Formation Interstate Purdy Depth to Top 4192 Bottom 4200 T.O. 4572

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1237	0
				5 1/2	4560	1450

KANSAS RECEIVED  
CORPORATION COMMISSION  
APR 28 1993  
CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Release pkr & pmp 2 sxs hulls & 25 sxs cmt from 3992-4192. TOH w/1000' of 2 7/8 tbg. TOH w/remaining 2 7/8 tbg. Load hole w/60 bbl mud. Shot 5 1/2 csg free @ 1450'. Pull 5 1/2 csg to 1260'. Pmp 50 sxs cmt from 1160-1260'. Pull 5 1/2 csg to 650'. Pmp 40 sxs cmt from 550-650'. Pull 5 1/2 csg to 40'. Pmp 20 sxs cmt from 0-40'. Rec 34 jts 5 1/2 csg.

(If additional description is necessary, use BACK of this form.) (Over)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547  
Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation


STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams  
(Address) Beverly J. Williams, Tech. Asst. P.O. Box 351, Liberal, KS 67905

\*Formerly JM Huber USA "C" No. 1.

SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 93  
(Cheryl Steers)

My Commission Expires:  CHERYL STEERS  
Notary Public