

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-129-21,023 - 0000

LEASE NAME GOODTHING

WELL NUMBER 1-28

4030 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 28 TWP. 34S RGE 43 (E) or (W)

COUNTY MORTON

Date Well Completed 2/17/90

Plugging Commenced 11/17/96

Plugging Completed 11/18/96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/13/96 (date)

by MR. STEVE DURANT (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation TOPEKA Depth to Top 2709' Bottom 2789' T.D. 3150'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
TOPEKA	GAS	2709'	2789'	12-1/4"	1505'	3'
				4-1/2"	3147'	1450'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
P&A'D AS FOLLOWS: MIX 2 SXS HULLS & 20 SXS CMT, PMP CMT FROM 2709-2509, ZONE TOOK CMT PLG, RE-PMPD 20 SXS FROM 2709-2509, SHOOT OFF 4-1/2" CSG @ 1450', CIRC HOLE W/MUD, MIX 50 SXS CMT & SPOT FROM 1700-1450, PULL 4-1/2 CSG TO 600', MIX 40 SXS CMT & SPOT FROM 600-500', PULL 4-1/2" CSG TO 40' & SPOT 10 SXS CMTG FROM 40-3'. CUT OFF 8-5/8" CSG 3' BELOW GL & CAP, REC 37 JTS 4-1/2" CSG. KCC WITNESS: STEVE DURANT

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman
JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 1997

Freda R. Hinz
 Notary Public

My Commission Expires:

