

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-20,341-0000

LEASE NAME Interstate Unit

WELL NUMBER 84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

5030 Ft. from S Section Line

5120 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 28 TWP. 34 SRGE. 43 (X) or (W)

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

COUNTY Morton

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 2-17-78

Character of Well Oil

Plugging Commenced 6-27-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-29-94

The plugging proposal was approved on 6-29-94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filled? Driller's Log Filed If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4180

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size  | Put In | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 1166   | 3'         |
|           |         |      |    | 5 1/2 | 4176   | 1220'      |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU csg pullers. Rel pkr and pull 2 7/8" tbg to 3884'. Set pkr. RU pmp truck. Pmp 2 sxs hulls and 25 sxs Class "H" cmt to plug perms from 4084-3884'. Rel pkr and circ hole w/9 ppg mud. TOH w/2 7/8" tbg and pkr. LD 130 its 2 7/8" tbg. Pull free point and shot 5 1/2" csg @ 1220'. Spot 45 sxs Class "H" cmt @ 1200-1050'; 30 sxs Class "H" cmt @ 650-550'. 10 sxs Class "H" cmt @ 40-0'.  
(If additional description is necessary, use BACK of this form.) (Over)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Leslie I. Barnes (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are correct, so help me God.

(Signature) Leslie I. Barnes  
Leslie I. Barnes, Sr. Tech. Asst.  
(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 1st day of August, 1994

C Cheryl Steers  
Notary Public

CHERYL STEERS  
Notary Public - State of Kansas  
My Appt. Expires 6-1-97

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 08 1994  
CONSERVATION DIVISION  
WICHITA, KS  
My Commission Expires