

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Morton

County. Sec. 28 Twp. 34S Rge. 43 (EX) (W)

Location as "NE/CNW%SW%" or footage from lines C NW/4 of SW/4

Lease Owner J. M. Huber Corp.

Lease Name Cole Well No. 1

Office Address Box 978, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-17-55 (Rotary) 7-31-55 (cable) 19

Application for plugging filed 8-4-55 19

Application for plugging approved 8-4-55 19

Plugging commenced 8-5-55 19

Plugging completed 8-5-55 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4685' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1198'	None
				5-1/2"	4602'	1324'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

7-31-55 & (Pumped 7 sacks of cement at 4528'. Filled up 50' to 4478' and  
8-4-55 (dumped 5 sacks at 4438'. Shot off and recovered 1324' of 5 1/2" casing.  
Filled hole with mud to 500'. Spotted 20 sacks cement on top  
of Halliburton plug. Filled hole with mud to 35' and capped  
hole with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Daco Well Service  
Address Borger, Texas

STATE OF KANSAS, COUNTY OF SEWARD, ss.  
W. W. Henson (employee of owner) or ( ) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 978, Liberal, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1955

My commission expires June 1, 1958 [Signature] Notary Public.

24-2675-S 2-52-20M

PLUGGING  
FILE SEC 28 T 34 R 430  
BOOK PAGE 142 LINE 45

8-16-55  
CONSERVATION DIVISION  
Wichita, Kansas

WELL LOGWELL NAME: Cole #1WELL LOCATION: Center of NW/4 of SW/4 of Section 28, Township 34S,  
Range 43W, Morton Co., Kansas.WELL OWNER: J. M. Huber Corp.DRILLING COMMENCED: 6-30-55DRILLING COMPLETED: 7-16-55WELL COMPLETED: 7-17-55 (Rotary)  
7-31-55 (Cable)Total Depth: 4685'

<u>FORMATION</u>	<u>DEPTH</u>
Clay, gyp, sand	0 - 150
Redbed	150 - 419
Redbed & shells	419 - 1180
Anhydrite	1180 - 1400
Anhydrite, redbed, shale	1400 - 1680
Redbed & shale	1680 - 1955
Shale	1955 - 2215
Lime & shale	2215 - 2260
Lime, redbed & shale	2260 - 2390
Lime & shale	2390 - 3850
Lime	3850 - 4053
Lime & shale	4053 - 4115
Lime	4115 - 4131
Lime & shale	4131 - 4180
Shale & sand	4180 - 4222
Lime & shale	4222 - 4275
Lime, shale & sand	4275 - 4375
Lime & shale	4375 - 4531
Sand & lime	4531 - 4622
Lime	4622 - 4685
Total Depth	4685


STATE OF KANSAS, COUNTY OF SEWARD, ss

W. W. Henson, employee of owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct.

*W. W. Henson*

Subscribed and sworn to before me this 15<sup>th</sup> day of August, 1955.

*James S. Tash*  
Notary Public



My commission expires: *June 1, 1958*