


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Morton County, Sec. 28 Twp. 34S Rge. 43 (W)
Location as "NE/CNW/SW" or footage from lines C SE SW NW
Lease Owner Cities Service Oil Company
Lease Name Roll A Well No. 1
Office Address 3545 N.W. 58th St., Oklahoma City, Oklahoma 73112
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 8-7 19 53
Application for plugging filed 8-6 19 75
Application for plugging approved 8-7 19 75
Plugging commenced 9-10 19 75
Plugging completed 9-11 19 75
Reason for abandonment of well or producing formation Uneconomical



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production February 19 75
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence F. Thomas
Producing formation Topeka Depth to top 2710 Bottom 3090 Total Depth of Well 3090 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Topeka	Gas	2950	2960	13-3/8"	520'	None
				5-1/2"	3089	1214'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spot 20 sack cement plug from 2900 to 3002. Pulled 9" stretch w/88,000#. Shot casing @1807', 1628', 1404, & 1214'. Pulled 42 joints of 5-1/2", 14#, 8rd German Casing, spotting mud & plugs as follows: Mud from 535' to 2900', 60 sack cement plug from 470' to 535', Mud from 40' to 470', 40 sack cement plug from 4' to 40'. Cut off 13-3/8" casing 4 feet below ground level & welded on steel cap w/well name & date.

9-24-75

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Daco Lease & Well Servicing
Address 1700 S. Main Berger, Texas

STATE OF Oklahoma, COUNTY OF Oklahoma
I, H. E. Massey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. E. Massey
Operations Manager
3545 N.W. 58th St., Oklahoma City, OK 73112
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of September, 19 75

My commission expires 4-2-77



Notary Public.

CITIES SERVICE OIL COMPANY

ROLL "A" #1

MORTON COUNTY, KANSAS

FORMATION	TOP	BOTTOM
Surface, Galy & Sd.	0	70
Lime & Sand	70	130
Red Bed & Shale	130	250
Sand, Shale & Gyp	250	485
Sand & Shale	485	534
Red Bed & Blue Shale	534	850
White Sand	850	1,000
Sand & Shale	1,000	1,161
Sand	1,161	1,190
Anhydrite	1,190	1,240
Sand, Shale & Dolo.	1,240	1,296
Sand & Shale	1,596	2,177
Lime & Shale	2,177	2,504
Lime & Shale	2,504	2,842
Lime	2,842	3,090
TD	3,090	

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1975

CONSERVATION DIVISION
Wichita, Kansas