

15-129-10317-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 7-10-57

LEASE NAME Interstate Unit

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 52

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 28 TWP. 34S RGE. 43 (E) or (W)

COUNTY Morton

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 7-10-57

Character of Well Inj.

Plugging Commenced 2-15-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-18-91

The plugging proposal was approved on 2-10-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Morrow Depth to Top 4123 Bottom 4136 T.D. 4200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1179	0
				5 1/2	4199	4140'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circ hole w/9.0 ppg mud. Spot 20 sx cmt + 2 sxs hulls @ 4123-4023, TOH w/2 3/8" tbg & pkr.

Ran freepoint & shot 5 1/2" csg @ 2412. Pull 5 1/2" to 1279 & spot 50 sxs cmt from 1279-1079. Pull csg to 650 & spot 25 sxs from 650-550. Pull csg to 50' & spot 10 sxs cmt from 50-3. Cut off & cap 8 5/8" csg 3' below ground level. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

Beverly J. Williams, Eng. Tech.

(Address) P.O. Box 351, Liberal, KS 67905-0351

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 1st day of March, 19 91

MAR - 4 1991

Cheryl Steers
Notary Public

CONSERVATION DIVISION
Wichita, Kansas My Commission Expires:

