

15-29-30009-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Morton County, Sec. 27 Twp. 34S R. 10E (E) 43 (W)

Location as "NE/CNW/SW" or footage from lines 660' FN&E lines

Lease Owner Pioneer Production Corporation

Lease Name H. D. Roll Well No. 1

Office Address P O Box 2542, Amarillo, Texas 79105

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 4-26-65 19

Application for plugging filed 5-8-68 19

Application for plugging approved 5-14-68 19


Plugging commenced 5-21-68 19

Plugging completed 5-22-68 19

Reason for abandonment of well or producing formation  
Well making salt water

If a producing well is abandoned, date of last production 5-1-68 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. E. Eves

Producing formation Morrow Depth to top 4256 Bottom 4310 Total Depth of Well 4658 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Wabaunsee	water	2542	2744	8-5/8	1174'	0
Topeka	water	2744	3122	2-7/8	4622	2800
Lansing-Kansas City	water	3122	4122			
Morrow shale	water	4122	4257			
Morrow sand	water-gas	4257	4310			
Keys sand	water	4540	4604			
Miss.	water	4630	4658			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 4 sx cement plug f/4065-4200'  
Filled hole w/mud  
Spotted 36 sx cement plug 500-600'  
Spotted 15 sx cement plug 0-50'  
Weld steel plate over top of casing

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 23 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service  
Address P O Box 506, Liberal, Kansas

STATE OF Texas COUNTY OF Potter, ss.  
J. A. Tipton (employed of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Tipton  
J. A. Tipton, Prod. Supt.  
P O Box 2542, Amarillo, Texas 79105  
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of May 1968

My commission expires June 1, 1969

Faye W. Kelley  
Notary Public, Potter County, Texas

DRILLER'S LOG

W.D. Roll #1  
 Loc: Center NE/4 NE/4  
 Sec: 27-345-43W  
 Morton County, Kansas  
 Company: Amarillo Oil Company

Comm: 3-24-65  
 Comp: 4-9-65  
 Rotary Tool Depth: 4658'  
 Casing: 8-5/8" @ 1174'  
 Tubing: 2-7/8" @ 4624'

Contractor: Davis Drlg., Inc.

0	100	Surface Sand
100	180	Sand & Clay
180	565	Red Bed Shale & Rock
565	675	Red Bed & Shale
675	795	Red Bed & Gyp.
795	1075	Sand, Shale & Gyp.
1075	1174	Shale & Gyp.
1174	1240	Lime & Shale
1240	1640	Shale & Red Bed
1640	1780	Red Bed & Shale
1780	1930	Shale
1930	2245	Shale & Lime
2245	2410	Lime & Shale
2410	2675	Shale & Lime
2675	3075	Lime & Shale
3075	3950	Sandy Lime
3950	4015	Lime
4015	4198	Lime & Shale
4198	4258	Shale
4258	4270	Sand
4270	4360	Sand & Shale
4360	4431	Shale & Sand
4431	4515	Shale, Lime, & Sand
4515	4580	Shale, Sand, & Lime
4580	4630	Sand & Lime
4630	4658	Shale & Lime
4658		Total Rotary Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 14 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

Cemented 8-5/8" casing at 1174' with 460 sacks of Pos-Mix with 4% jel, 2% Calcium Chloride and 100 sacks 6040 3% HA5

2-7/8" tubing cemented at 4624' with 375 sacks common cement, 4% jel, 12 1/2 lbs. Gilsonite per sack.

I certify that this is the true and correct copy of the above log to the best of my knowledge.

*Kenneth G. Fischer*  
 Kenneth G. Fischer, Sec'y.

Subscribed and sworn to before me this 14<sup>th</sup> day of April, 1965/

My commission Expires:  
March 8, 1967

*James Ann Wilson*  
 Notary Public