

15-129-10555-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 9-25-55 Drill Date _____

LEASE NAME Roll

WELL NUMBER 1-27

3960 Ft. from S Section Line

3955 Ft. from E Section Line

SEC. 27 TWP. 34S RGE. 43 XR or (W)

COUNTY Morton

Date Well Completed 10-10-55

Plugging Commenced 1-18-94

Plugging Completed 1-20-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-13-94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation Topeka Depth to Top 2749 Bottom 2858 T.D. 3027

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	587	0
				5 1/2	3027	927

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH w/1 1/4 tbg to 2749. Spot 2 sxs gel, 2 sxs hulls & 25' sxs cmt from 2749-2549. Circ hole w/mud. TOH w/1 1/4 tbg. Shot csg off @ 927 & TOH. TIH w/1 1/4 to 800, hit bridge. Spot 30 sxs cmt plug from 800-700. Pulled 1 1/4 to 610. Circ hole w/mud. Spot 50 sxs cmt from 610-460. TOH & spot 10 sxs cmt plug from 40-0. Cut off csg 3' below ground level & cap. KCC witnessed. Restore
(If additional description is necessary, use BACK of this form.) location.

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, Oklahoma 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED

KANSAS CORPORATION COMMISSION

1-28-94

JAN 28 1994

SUBSCRIBED AND SWORN TO before me this 27th day of January, 1994

CONSERVATION DIVISION

WICHITA, KS

My Commission Expires:

(Signature) Beverly J. Williams

(Address) Beverly J. Williams, Technical Asst.
P.O. Box 351, Liberal, KS 67905-0351

Cheryl Steers
Notary Public

