

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

API NUMBER 15-129-10526 - 0001

LEASE NAME KANSAS

WELL NUMBER 1-24

1320 Ft. from N Section Line

1320 Ft. from W Section Line

SEC. 24 TWP. 34 RGE 43 ~~1E~~ or (W)

COUNTY MORTON

Date Well Completed 11-01-1957

Plugging Commenced 06-22-00

Plugging Completed 06-24-00

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-19-2000 (date)

by GARY WINTERS (KCC District Agent=s Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation WABAUNSEE Depth to Top 2553 Bottom 2644 T.D. 3010

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
WABAUNSEE	GAS	2553	2644	7"	590	0
				4-1/2"	2965	920

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
SPOT 2 SXS HULLS & 20 SXS CMT @ 2553-2353. RU JACKS. MEASURED STRETCH. 4-1/4" CSG UNSCREWED. RECONNECTED & SHOT OF 4-1/2" @ 920. CSG UNSCREWED @ 150. TOH W/ 6 JYS CSG. WELD ON GUIDE SHOE AND RECONNECTED TO CSG. SHOT OF @ 718. TOH TO 640. LOAD HOLE W/ MUD. SPOT 80 SXS CMT @ 640-240. TOH SPOT 10 SXS CMT FROM 50 TO SURE. CUT OFF AND CAP 7" CSG 3' BELOW GL/.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31154 **RECEIVED**
STATE CORPORATION COMMISSION

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION **1111 07 2000**

STATE OF KANSAS COUNTY OF SEWARD, ss. **CONSERVATION DIVISION**


SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 30th day of June, 2000.

My Commission Expires: _____



Notary Public

Form CP-4
Revised 05-88