

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129. 20044.00 .01

LEASE NAME KANSAS

WELL NUMBER 2-23

1980 Ft. from S Section Line

3000 Ft. from E Section Line

SEC. 23 TWP. 34 RGE 43 (E) or (N)

COUNTY MORTON

Date Well Completed 4-30-1972

Plugging Commenced 5-20-2002

Plugging Completed 5-21-2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-10-2002 (date)

by STEVE DURRANT (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation GLORIETTA Depth to Top 910 Bottom 920 T.D. 1099

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
GLORIETTA	NaCl H2O	910	920	8 5/8	1179	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
LOAD HOLE WITH 9 PPG MUD. PUMP 50 SXS CMT FROM 865 TO 715. PUMP 50 SXS CMT FORM 325 TO 175. SPOT 10 SXS FROM 34 TO 4. CUT OFF AND CAP 8 5/8 CSG 4' BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.
CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters

CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101



SUBSCRIBED AND SWORN TO before me this 17 day of June, 2002

Lori Pearson
Notary Public

My Commission Expires: 2/26/05

OR