

15-129-10196-0000


# WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Morton County, Sec. 22 Twp. 34 Rge. (E) 43 (W)

Location as "NE/CNWSW" or footage from lines C SE NW  
Lease Owner Anadarko Production Company  
Lease Name Interstate "G" Well No. 1  
Office Address P. O. Box 351, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 8 19 62  
Application for plugging filed August 7 19 62  
Application for plugging approved August 7 (verbal) 19 62  
Plugging commenced August 7 19 62  
Plugging completed August 8 19 62  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2100 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	604	
				4 1/2	1313	797

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 100 sacks common cement down 4 1/2" casing. Displaced to 895' at 2000# pressure. Shot off 4 1/2" casing at 797'. Rilled casing. Filled hole with mud to 600'. Spotted 20 sacks cement. Filled hole with mud to 50'. Spotted 15 sacks cement to surface. Complete at 6:00 p.m. August 8, 1962.

STATE PLUGGING DIVISION  
8-16-62  
1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent Casing & Pulling Crews  
Address Liberal, Kansas

STATE OF KANSAS COUNTY OF SEWARD, ss.  
S. H. Neithercoat (employee of owner) or owner/operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. H. Neithercoat  
P. O. Box 351, Liberal, Kansas  
(Address)

Subscribed and sworn to before me this 15th day of August, 19 62

Mary Beth Gray  
Notary Public.  
Mary Beth Gray

My commission expires July 24, 1965

My commission expires \_\_\_\_\_

15-129-10196-0000

DRILLER'S LOG

WELL NAME Interstate "G" #1

COMPANY OPERATING Anadarko Production Company  
 ADDRESS of COMPANY Box 351, Liberal, Kansas

WELL LOCATION C 1/2 SE 1/2 NW 1/2,

3300 ft. North of South line,

1980 ft. East of West line; Sec. 22 Twp. 34S Rge. 43W, Morton County, Kansas

DRILLING STARTED June 16, 19 62

DRILLING COMPLETED June 21, 19 62

WELL COMPLETED August 8, 19 62

WELL CONNECTED \_\_\_\_\_, 19 \_\_\_\_\_

ELEVATION 3453 ft. Ground Level

CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
NONE					

REGISTERED  
 STATE CORPORATION COMMISSION  
 AUG 10 1962  
 CONSERVATION DIVISION  
 Liberal, Kansas

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8	604	350	
4 1/2	1313	75	797

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Open Hole	0	45	Sand Shale	1870	2013
Cement	45	57	Shale	2013	2100
Red Bed	57	350	Total Depth	2100	
Red Bed & Shale	350	608			
Red Bed & Anhydrite	608	720			
Anhydrite	720	740			
Sand	740	900			
Red Bed	900	1140			
Red Bed, Anhydrite & Sand	1140	1280			
Red Bed & Shale	1280	1540			
Red Bed, Shale & Anhydrite	1540	1710			
Shale & Lime	1710	1870			

RESULTS of INITIAL PRODUCTION TEST: Well has been plugged and abandoned.