

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1965
8-30-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill McKeen of Wm. Gruenerwald has this

date requested permission to plug the following described well:

Mr. McKeen guarantees payment of the plugging fee.

Operator's full Name: Wm. Gruenerwald & Assoc.

Complete Address: Box 909, Colorado Springs, Colorado

Lease Name: Warden Well No. # 1

Location: NE NW Sec. 30 Twp. 34 Rge. 32 (E) (W) W

County Seward Total Depth 6386' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. McKeen was instructed to plug the well as follows:

1586' of 8 5/8" surface pipe, cement circulated with 700 sacks.
Fill hole with drilling mud. Spot 25 sacks of cement at 1500',
through the drill pipe. Spot 25 sacks of cement at 600', through
the drill pipe. Fill hole with drilling mud to 45', bridge plug
with hulls, and cement with 15 sacks.

Very truly yours,

Archie Elving