

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1966
CONSERVATION DIVISION
WICHITA, KANSAS
10-24-66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Mallomee-Coppinger has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Mallomee-Coppinger Operations Inc.

Complete Address: 1207 Union Nat'l Bldg., Wichita, Kansas

Lease Name: Warden Well No. 1

Location: C NE NE Sec. 30 Twp. 34 Rge. 32 (E)(W)

County Seward Total Depth 6560' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1298' circulated w/ cement. 1/2" to 5253' cemented,

Top Perforations 5198' Plug bottom w/ 20 sacks cement.

Top of cement 5000' Mud 5000' to 700'

Spotted 40 sacks cement 700' to 580' Mud 580' to 35'

Plug, Hulls & 10 sacks cement 35' to 0'

Very truly yours,

Edgar J. Eves
Conservation Division Agent