

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Patrick of Petroleum Inc. has this

date requested permission to plug the following described well:

Mr. Patrick guarantees payment of the plugging fee.Operator's full Name: Petroleum Inc.,Complete Address: Box 1255, Liberal, KansasLease Name: Warden "E" Well No. 1Location: C NE SW Sec. 30 Twp. 34 Rge. 32 (E) (W)County: Seward Total Depth 6378' Oil Well XGas Well Input Well SWD Well D & A X Lost Hole Mr. Patrick was instructed to plug the well as follows:8 5/8" to 1580' circulated w/ cement. 4 1/2" to 6378' cemented.Top perforations 5198' Plug bottom w/ 20 sacks cement.Top of cement 5000' Mud 5000' to 800'Spot 35 sacks cement 800' to 700' Mud 700' to 45'Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent