

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Anadarko has this

date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351, Liberal, Kansas

Lease Name: McAhren "C" Well No. 1

Location: C NE NW Sec. 24 Twp. 34 Rge. 33 (E)(W)

County: Seward Total Depth 6413' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hanna was instructed to plug the well as follows:

8 5/8" to 1570' circulated w/ cement. 4 1/2" to 6412' cemented.


Top perforations 6324' Plug bottom w/ 20 sacks cement.

Top of cement 6224' Mud 6224' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, H₁₁s & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent