

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 8 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Alpar has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Alpar Resources, Inc.

Complete Address: Box 906, Perryton, Texas

Lease Name: Wright Well No. 1

Location: NE SE Sec. 23 Twp. 34 Rge. 33 (E)(W)

County: Seward Total Depth 6700' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1621' circulated w/ cement. 4 1/2" to 6689' cemented.


Top perforations 5362' Plug bottom w/ 20 sacks cement.

Top of cement 5100' Mud 5100' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent