



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Nenney of Cities Service Oil has this date requested permission to plug the following described well:

Mr. Nenney guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1098, Liberal, Kansas

Lease Name: Salley "C" Well No. 2

Location: NE SW Sec. 16 Twp. 34 Rge. 33 XX (E) (W)

County: Seward Total Depth 6414' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Nenney was instructed to plug the well as follows:

8 5/8" to 2794' circulated w/ cement. 5 1/2" to 4475' cemented.

Top perforations 4034' Plug bottom w/ 20 sacks cement.

Top of cement 3800' Mud 3800' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'.

Plug, Hulls & 15 sacks cement 45' to 0'.

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1970

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent