

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Vaughn has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Jack H. Vaughn Engineering Company

Complete Address: 708 1st National Center, Oklahoma City, Oklahoma

Lease Name: Hays "A" Well No. 1

Location: App G SW Sec. 4 Twp. 34 Rge. 31 (E) (W)

County: Seward Total Depth 6000' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1455' circulated w/ cement. 4 1/2" to 5770' cemented.

Top perforations 5645' Plug bottom w/ 20 sacks cement

Top of cement 5545' Mud 5545' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent