



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1965
3-30-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Mahoney of A.J. Curtiss & Mahoney has this date requested permission to plug the following described well:

Mr. Mahoney guarantees payment of the plugging fee.

Operator's full Name: A.J. Curtiss & Mahoney

Complete Address: Box 1257 Liberal, Kansas

Lease Name: Dowdy Well No. " 1-31

Location: C NW SE Sec. 31 Twp. 34 Rge. 34 (E)(W)

County Seward Total Depth 6752' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mahoney was instructed to plug the well as follows:

13 3/8"-735' Circulated w/cement. 9 5/8" 2905' Cemented.

4 1/2"-6750'-Cemented. Bridge plug at 4400'. Perforations 4360' to 4365'

Plug bottom w/20 Sax.cement top cement 4178'. Mud 4178' to 700'

Spotted 35 Sax.cement 700' to 600' Mud 600' to 45'

Plug, Hulls, 15 "ax.cement 45' to 0

Very truly yours,

Conservation Division Agent