



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

14 April 1982

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1982

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-175-20619

Dear Sir:

Mr. John Hanna of Anadarko Production Co. has this date requested permission to plug the following described well:

Operator's Full Name: Anadarko Production Co.

Complete Address: Box 351, Liberal, Kansas 67901

Lease Name: Carr Well No. A1

Location: C-SW-SW-SE Sec. 5 Twp. 34 Rge. 34 (E) (W)

County: Seward Total Depth: 6600'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Hanna was instructed to plug the well as follows:

1st plug at 2650' with 25 Sbs of cement. 2nd plug at 1700' with 70 Sbs of cement. 3rd plug at 800' with 35 Sbs of cement. 4th plug 40' to 0' with 10 Sbs of cement. Then circulate 10 Sbs of cement in rat hole & 5 Sbs of cement in mouse hole. Then 3 Sbs of cement in water well. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Halliburton Co. They had run 1675' of 8 5/8" surface casing cement circulated.

Very truly yours,

Paul A. Luthi
Conservation Division Agent