

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
OCT 26 1973  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Coffin of Wilmar has this

date requested permission to plug the following described well:

Mr. Coffin guarantees payment of the plugging fee.Operator's full Name: Wilmar Oil CompanyComplete Address: Box 474, Mattoon, IllinoisLease Name: McNill-Nix Well No. 1Location: C SW NE Sec. 4 Twp. 34 Rge. 34 XX (E) (W)County: Seward Total Depth 6550' Oil Well XGas Well      Input Well      SWD Well      D & A      Lost Hole     Mr. Coffin was instructed to plug the well as follows:8 5/8" to 1696' circulated w/ cement. 5 1/2" to 6530' cemented.Top perforations 6338' Plug bottom w/ 20 sacks cement.Top of cement 5621' Mud 5621' to 1000'Spot 35 sacks cement 1000' to 900' Mud 900' to 45'Plug, Hulls <sup>o</sup> 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent