

To: 020771
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-21,631-0000
NW SE SE, SEC. 14, T 34 S, R 37 W/X
1250 feet from S section line
1250 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5208
Operator: Mobil Oil Corporation
Name:
Address: P.O. Box 2173
Liberal, KS 67905-2173

Lease Name McCreery #1 Unit Well # 3
County Stevens
Well Total Depth 3005 97.66 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 650

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382
Address P.O. Box 916, Garden City, KS 67846-0916

Company to plug at: Hour: 3:10 p.m. Day: 23 Month: 6 Year: 19 94

Plugging proposal received from Jeff Lasiter
(company name) Mobil Oil Corporation (phone) 316-626-1160

Work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 1720' with 50 sx cement,
2nd plug at 670' with 50 sx cement, 3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 12 a.m. Day: 24 Month: 6 Year: 19 94

ACTUAL PLUGGING REPORT Pipe stuck, couldn't get down to TD.
1st plug at 1720' with 50 sx cement,
2nd plug at 670' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell.
(If additional description is necessary, use BACK of this form.)

(XXX) / did not observe this plugging.
6-29-94
40709
6-24
Signed Glenn R. Barton (TECHNICIAN)
STATE CORPORATION COMMISSION
JUN 2 1994
FORM C
CONSERVATION DIVISION
Wichita, Kan.

CARD MUST BE TYPED

NOTICE OF INTENTION TO DRILL
HUCOTON INFILL

Starting Date: May 13 1994

API Number 15-189-2163

IS SECTION REGULAR IRRREGULAR:

Operator License # 5208

Name: Mobil Oil Corporation

Address: P.O. Box 2173, Liberal, KS 67905-2173

City/State/Zip: Liberal, KS 67905-2173

Contact Person: Rae Kelly (316)626-1160

Phone: (316)626-1160

CONTRACTOR License # Will address on ACO-1 RECEIVED

Name: Stevens

City/State: State Corporation Commission #1 Unit 14

Well Drilled as: New Recombination

Projected Total Depth: 3000

Formation: Chase

If OWWO or Recombination add well info as follows:

Operator: Conservation Division - face pipe by Alternates

Well Name: Wichita, Kansas

Camp Date: Old Total Depth: 620

Water Source for Drilling Operations: well farm pond other

DWR Permit #: 620

Regulatory Technician: Title

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date: 5-3-94

Signature of Operator or Agent: Rae Kelly

For KCC Use: Conductor Pipe Required: 116.5 ft. Minimum Surface Pipe Required: 620 feet per Alt.

This Authorization Expires: 11-5-94

Pusher: Jeff Lasiter
SPUD DATE: 6-15-94 INIT. OR
LENGTH SURFACE PLANNED: 650

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2 @ 650 CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD 3005 FORMATION 50 PRE STUCK @ 2620

RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1720 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 670 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond) Hauling

TECHNICIAN S.M. DATE 6-23-94

TYPE OF CEMENT 60/40 6%

STARTING TIME 3:10 (AM/PM) DATE 6-23-94

COMPLETION TIME 12: (AM/PM) DATE 6-23-94

CEMENT COMPANY Lowell

RECEIVED
STATE CORPORATION COMMISSION
JUN 9 1994

CARD MUST BE TYPED