

To: 1 110002  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 15-185-10053-0000  
Comp. 12-17-64

C SW NE, SEC. 13, T 34 S, R 37 W 5

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Operator: Mobil Oil Corporation  
Name &  
Address Box 5444 Term. Annex  
Denver, CO 80217

3300 feet from S section line

1980 feet from E section line

Cunningham Unit 1-26  
Lease Name \_\_\_\_\_ Well # B1

County Stevens 224.68

Well Total Depth 6913 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1773

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Patrick Well Service License Number 7547

Address Box 1273, Liberal, KS 67901

Company to plug at: Hour: 9:00 am Day: 26 Month: July Year: 19 85

Plugging proposal received from Tom Romero

(company name) Mobil (phone) 316-624-4901

were: 4 1/2" at 6913' PBSD 6450' Perfs at 6313-6351

1st plug set CIBP at 6300' and dump 5 sx cement on top of plug.

2nd plug pump 100 sx cement at 3034' (Class H)

3rd plug Perforate at 1834 and pump 525 sx cement (50/50 Pozmix)

4th plug circulate cement to surface

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 3:30 pm Day: 30 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6300' and dumped 5 sx cement on top of plug.

2nd plug perforated at 1834' and pumped 12 bbls mud and 525 sx cement (7-29-85). Ran

temperature survey showing a hole in the casing and surface pipe.

(7-30-85) Started pumping 400 sx cement - pressured up on annulus. Perforated at 1400',  
pressured up to 1500 lb. Circulated 425 sx cement to top. Cut off 4' below ground level

and capped. Circulated cement down annulus up through 4 1/2" to surface.

Remarks Used Class H and 50/50 Pozmix by Halliburton. No Recovery.  
(If additional description necessary, use BACK of this form.)

INVOLVED RECEIVED  
STATE CORPORATION COMMISSION  
observe this plugging.

AUG 5 1985 Signed James P. Papp  
(TECHNICIAN)

DATE \_\_\_\_\_

INV. NO. 9401  
7-30

Wichita, Kansas