

1000-000

15-189-20006-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-Not Available

SW SW NE NE, SEC. 13 27, T 34 S, R 37 22 W/R

660 FSL feet from SE Corner of section line

4620 FEL feet from SE Corner of section line

Cunningham

Lease Name ~~State~~ UT Well # 3

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Operator: Mobil Oil Corporation

Name & Address: Box 5444 Term. Annex

Denver, CO 80217

County: Stevens

Well Total Depth: 6913 224.67 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1755

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Midwest Casing Pulling License Number: 6497

Address: Box F, Sublette, KS 67877

Company to plug at: Hour: 9:00 am Day: 8 Month: October Year: 19 84

Plugging proposal received from: Chris Lister

(company name): Mobil (phone) 316-624-4901

were: 4 1/2" set at 6914' PBTD 6862' Perfs at 6350'-6774'

1st plug pump mud to 6708' and pump 2 sx hulls and 10 sx cement to bottom

2nd plug pump mud to 6313' and pump 10 sx cement

3rd plug pump mud to 3325' and pump 10 sx cement

4th plug pump mud to 2600' and pump 10 sx cement

5th plug pump mud to 1740' and pump 50 sx cement, 6th plug pump mud to 750' and pump 10 sx cement, 7th plug pump mud to _____

40' - solid bridge - pump 8 sx cement.

Plugging Proposal Received by Paul A. Luttin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11:00 am Day: 13 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 6914' PBTD 6862' Perfs at 6350-6774'

1st plug pumped mud to 6708' and pumped 2 sx hulls and 10 sx cement to bottom, 2nd plug

pump mud to 6313' and pumped 10 sx cement, 3rd plug pumped mud to 3325' and pumped 10 sx

cement, 4th plug pumped mud to 2600' and pumped 10 sx cement, 5th plug pumped mud to

1740' and pumped 50 sx cement, 6th plug pumped mud to 750' and pumped 10 sx cement

7th plug pumped mud to 40' - solid bridge - pumped 8 sx cement.

Remarks: Recovered 1934' of 4 1/2" casing. Used Common Sacked Cement by Midwest.

(If additional description is necessary, use BACK of this form.)

I (did / ~~xxxxxx~~) observe this plugging.

Signed Paul A. Luttin (TECHNICIAN)

10-18-84

4400

10-13 NOV 19 1984