

1086281

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-189-20,727-0000

NW SW, SEC. 6 T 34 S, R 37 W  
N SE Corner of  
1980 feet from ~~XXXX~~ section line  
W SE Corner of  
4620 feet from ~~XXXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Lease Name Kimzey Well # B-2

Operator: Anadarko Production Co.

County Stevens

Name & Address Box 351

Well Total Depth 6700 217.75 feet

Liberal, KS 67901

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1707

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gabbert-Jones, Inc. License Number 5843

Address 830 Sutton Place, Wichita, KS 67202

Company to plug at: Hour: 7:00 pm Day: 20 Month: July Year: 19 84

Plugging proposal received from Jim Barlow

(company name) Gabbert-Jones (phone) 316-263-6209

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2600' with 70 sx cement

2nd plug at 1750' with 50 sx cement

3rd plug at 860' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthie  
(TECHNICIAN)

7th plug to circulate mouse hole with 10 sx cement

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:30 pm Day: 20 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2600' with 70 sx cement, 2nd plug at 1750' with 50

sx cement, 3rd plug at 860' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 15 sx cement.

Remarks: Used Common sacked cement 2% gel 3% cc by Western

(If additional description is necessary, use BACK of this form.)

(~~XXX~~ / did not) observe this plugging.

7-27-84

Signed Paul A. Luthie  
(TECHNICIAN)

2710

7-20

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 24 1984  
CONSERVATION DIVISION  
Wichita, Kansas