

1 180542

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 189-20,646-0000  
SE , SEC. 35 , T 34 S, R 38 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Operator: Anadarko Production Company  
Name & Address: P.O. Box 351  
Liberal Kansas 67901

2540 feet from S section line  
1250 feet from E section line

Lease Name K.U. Endowment "C" Well # 1

County Stevens 101.40

Well Total Depth 3120 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 727'

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Western Co. of N. America License Number \_\_\_\_\_

Address Box AA Perryton Texas 79070

Company to plug at: Hour: 11:45 am Day: 30 Month: May Year: 1985

Plugging proposal received from Chuck Nelson

(company name) Anadarko (phone) 316-624-6253

were: 4 1/2" production casing set 3119' PBTB 3098' Perfs at 2992 to 3025'

Fill entire 4 1/2" casing with 260 sacks of 60/40 pozmix 2% gel 3% cc cement,

If annulus is open fill it with cement also.

Plugging Proposal Received by Bob Tarbutton KDHE  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:00pm Day: 30 Month: May Year: 1985

ACTUAL PLUGGING REPORT Cemented 4 1/2" casing with 260 sx of 60/40 pozmix 2% gel 3% cc

Filled 8 5/8" surface pipe w 20 sx

Plate welded on 8 5/8"

Glen Barlow witnessed the entire plugging procedure.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 07 1985

Remarks: (If additional description is necessary, use BACK of this form.)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (did not) observe this plugging.

DATE 6-12-85

Signed Richard W. Lacy  
(TECHNICIAN)

INV. NO. 8446  
5-30